

WARZYN

**Report
15340.02**

**Landfill Cover Design
Remedial Design/Remedial Action
Source Control Operable Unit
Hagen Farm Site
Town of Dunkirk, Wisconsin**

Prepared for:
**Waste Management of Wisconsin, Inc.
Westchester, Illinois**

Prepared by:
**Engineering Group
Waste Management of North America, Inc.
Oak Brook, Illinois**

**Warzyn Inc.
Madison, Wisconsin**

July 1991



Appendix C
Operation and Maintenance Plan

Landfill Cover Design Report
Remedial Design/Remedial Action
Source Control Operable Unit
Hagen Farm Site
Town of Dunkirk, Wisconsin

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

Table of Contents

| | | |
|-------|--|----|
| 1.0 | Introduction..... | 1 |
| 2.0 | Elements Included in O&M Plan..... | 3 |
| 3.1 | Soil Cap Design Elements | 3 |
| 3.2 | Appurtenant Design Elements | 4 |
| 3.0 | Normal Operation and Maintenance | 5 |
| 3.1 | Operation Tasks..... | 5 |
| 3.2 | Maintenance Tasks..... | 5 |
| 3.2.1 | Restoration of Soil Cap | 5 |
| 3.2.2 | Vegetation Establishment and Cultivation..... | 6 |
| 3.2.3 | Sediment Removal in Erosion and Stormwater Control Structures | 7 |
| 3.2.4 | Repair of Erosion and Stormwater Control Structures | 7 |
| 3.3 | Maintenance Schedule..... | 7 |
| 4.0 | Routine Monitoring..... | 9 |
| 4.1 | Monitoring Tasks | 9 |
| 4.2 | Required Testing..... | 9 |
| 4.3 | Monitoring Frequency..... | 9 |
| 5.0 | Alternate Operation and Maintenance..... | 11 |
| 6.0 | Safety During Maintenance | 13 |
| 7.0 | Required Equipment..... | 15 |
| 8.0 | Operation and Maintenance Annual Budget..... | 17 |
| 9.0 | Recordkeeping | 19 |

Tables

| | | |
|-----------|------------------------------------|----|
| Table C-1 | Minimum Maintenance Frequency..... | 8 |
| Table C-2 | Minimum Monitoring Frequency | 10 |
| Table C-3 | Maintenance Annual Budget..... | 17 |

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

1.0 INTRODUCTION

This Operation and Maintenance Plan (O&M Plan) has been prepared in conjunction with the Remedial Design/Remedial Action Design Report for the Landfill Cover Design at the Hagen Farm Site, Dane County, Wisconsin. The O&M Plan provides guide-lines for long-term maintenance of each component of the Landfill Cover Design. Post-closure care for the Landfill Cover Design elements will be performed in compliance with Wisconsin Administrative Code (WAC), Department of Natural Resources Rules of Solid and Hazardous Waste Management.

The design of the landfill cover has followed the Record of Decision, the Scope of Work, the provisions of the Unilateral Administrative Order, and the U.S. EPA Superfund RD/RA Guidance.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

2.0 ELEMENTS INCLUDED IN O&M PLAN

Only those elements addressed in the Landfill Cover Design Report are included in this O&M Plan. Operation and maintenance of the *In Situ* Vapor Extraction portion of the Source Control Operable Unit and of the Groundwater Control Operable Unit will be discussed under separate documents.

A detailed description of the Landfill Cover Design is presented in the Landfill Cover Design Report. Implementation of the Construction Quality Assurance Plan (Appendix F) will document that the soil cap construction meets or exceeds construction requirements. In addition, the Specifications (Appendix B) and Design Plans (Appendix A) for the construction of the Landfill Cover Design elements will be of sufficient quality to minimize maintenance.

3.1 Soil Cap Design Elements

A multi-layer soil and geotextile cap will be constructed over Area A. The cap is designed and will be constructed according to the minimum requirements of NR 504.07 (1)-(7) WAC. In accordance with the Feasibility Study Report and the ROD, the cap design has been modified from NR 504.07 (1)-(7) WAC to include a drainage layer and associated geotextiles. The cap will have the following profile (listed from ground surface, downward).

- A minimum 0.5-foot thick vegetative layer (topsoil) that will sustain plant growth that will aid in the prevention of erosion providing protection to the remainder of the cap.
- A minimum 1.5-foot thick rooting zone layer aiding in providing protection from frost penetration and preventing roots from the vegetative layer from damaging the low-permeability portion of the cap.
- A non-woven geotextile providing filtering and separation between the neighboring soil layers.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

- A minimum 1.0-foot thick drainage layer that will reduce the potential for head build-up on the low permeability layer due to high infiltration events by promoting drainage.
- A low permeability, compacted clay layer to minimize infiltration. This layer will be a minimum 2.0 feet thick and will have a maximum saturated hydraulic conductivity of 1×10^{-7} cm/sec.

A detail showing the cap profile is on Sheet No. 5, Cross Sections and Details, Drawing No. 15340-F5 in Appendix A, Design Plans.

3.2 Appurtenant Design Elements

In addition to the soil cap, the following elements will be constructed as part of the landfill cover design.

- A drainage swale, culverts, and sedimentation basin will be constructed to provide erosion protection for the surrounding property from discharges from the area of the soil cap.
- A six-foot high chain link fence topped with three-strand barbed wire will be constructed to prevent uncontrolled access and vandalism. Gates will be included for authorized access. Warning signs will be posted at 200 foot intervals along the fence and on each gate.

The location of these appurtenant structures is shown on Sheet No. 4, Proposed Final Grades, Drawing No. 15340-F4, in Appendix A, Design Plans.

Following placement of the soil cap and appurtenant design elements, disturbed areas will be seeded, fertilized and mulched.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

3.0 NORMAL OPERATION AND MAINTENANCE

3.1 Operation Tasks

No tasks are required for the operation of the soil cap. The surface water management features have been designed as passive systems that do not require human involvement for normal operation. No scheduling of operation tasks is required.

As there are no tasks required for the landfill cover system, there are no anticipated operational problems.

3.2 Maintenance Tasks

Maintenance tasks for the landfill cover system will include the following.

- Restoration of soil cap.
- Vegetation establishment and cultivation.
- Sediment removal in erosion and stormwater control structures.
- Repair of erosion and stormwater control structures.

A detailed description of each activity follows.

3.2.1 Restoration of Soil Cap

Restoration of the soil cap will be required if any of the following items are identified during routine monitoring of the soil cap.

- Gullies or rills on the surface of the soil cap formed by erosion that are greater than 2 inches in depth.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

- Areas of subsidence that form depressions or otherwise impair the performance of the cap in preventing infiltration.

Restoration of the cap would include placing the required soils material to achieve the original profile and requirements of the soil cap design. Vegetation would be re-established over the repaired areas. If significant erosion is expected to occur before vegetation is established, silt fences would be placed down-slope of the area under repair.

3.2.2 Vegetation Establishment and Cultivation.

Fertilizing, reseeding and mulching will be performed as required each spring to promote good vegetative growth. Based on visual inspection of vegetation, fertilizer type and application rate will be determined to meet the guide-lines provided by Section 630 of the *Wisconsin Department of Transportation, Standard Specifications* and the *Waste Management, Inc.; Landfill Vegetation Manual*.

Reseeding will be performed over areas where maintenance activities have disturbed the soil or areas greater than 8 feet in diameter where vegetation coverage is less than 75 percent. The seed mixture will be identical to that used for the original seeding unless the grass seed mixture appears to be ineffective. If required, the seed mixture will be modified in consultation with the Soil Conservation Service.

Mulching will be performed as required under the guide-lines provided by Section 627 of the *Wisconsin Department of Transportation, Standard Specifications*.

Mowing will be performed at least once during the annual growing season to inhibit the growth of detrimental plant species with penetrating roots (*i.e.*, trees with tap roots). Additional mowing will be performed if vegetation is matted down due to excessive height that would reduce the retarding of surface water run-off, or if vegetation becomes overgrown and a nuisance. Noxious weeds will be controlled with timely, approved herbicide application, through consultation with the Soil Conservation Service, and by mowing.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

3.2.3 Sediment Removal in Erosion and Stormwater Control Structures

As desired, eroded sediments from the landfill cover system features will accumulate in the drainage swales and sediment basin. If reduced capacity is identified in the drainage swales, or if the level of sediment rises above the sediment storage level in the basin (El. 864.0 NGVD), the sediment will be removed by excavation. The sediment will be excavated when it is as dry as possible and dispersed uniformly over the soil cap area. Care will be taken not to damage existing vegetation. If necessary, the material will be stockpiled and vegetated, to be used for maintenance of the Site when required.

3.2.4 Repair of Erosion and Stormwater Control Structures

If damage is identified to the erosion and stormwater control structures during inspection of the site, repairs shall be made to return the structures to the originally constructed condition.

3.3 Maintenance Schedule

Table C-1 shows the minimum required frequency for maintenance activities for the landfill cover system.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

Table C-1
MINIMUM MAINTENANCE FREQUENCY
Operation and Maintenance Plan, Landfill Cover RD/RA

| <u>Maintenance Activity</u> | <u>Minimum Frequency</u> |
|---|------------------------------------|
| Restoration of soil cap | As required |
| Vegetation establishment and cultivation | As required |
| Mowing | Minimum once during growing season |
| Sediment removal in erosion and stormwater control structures | As required |
| Repair of erosion and stormwater control structures | As required |

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

4.0 ROUTINE MONITORING

4.1 Monitoring Tasks

Two items of the landfill cover system require monitoring for appropriate maintenance. The soil cap of the landfill should be monitored for suitable vegetative cover, absence of erosion rills or gullies, depressions, and damaging subsidence. The erosion and sediment control structures should be monitored for excess sediment, flood damage, clogging by debris, or sparse vegetation.

4.2 Required Testing

Testing of the topsoil will be performed as required by visual inspection of the vegetation to determine appropriate fertilizer and lime application rates. Testing parameters will be the same as specified for the original seeding activity.

No other testing will be required for maintenance of the landfill cover system.

4.3 Monitoring Frequency

The following schedule outlines the required monitoring frequency for each monitoring task.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

Table C-2
MINIMUM MONITORING FREQUENCY
Operation and Maintenance Plan, Landfill Cover RD/RA

| <u>Monitoring Activity</u> | <u>Minimum Frequency</u> |
|---|--------------------------|
| SOIL CAP | |
| • Suitable Vegetative Cover | Semi-annually |
| • Absence of erosion rills or gullies | Semi-annually |
| • Depressions | Semi-annually |
| • Damaging Subsidence | Semi-annually |
| EROSION AND SEDIMENT CONTROL STRUCTURES | |
| • Excess Sediment | Semi-annually |
| • Flood Damage | After major storms |
| • Clogging by Debris | Semi-annually |
| • Sparse Vegetation | Semi-annually |

OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE

5.0 ALTERNATE OPERATION AND MAINTENANCE

As recommended in the Superfund Remedial Design and Remedial Action Guidance, U.S. EPA, June 1986, this section should address alternative operational and maintenance alternatives in case of failure of the landfill cap. No alternate operation and maintenance procedures are recommended because if the landfill cover was to fail, it would be repaired. The maintenance activities proposed for the landfill cover are sufficient to prevent failure of the cap.

1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50
 51
 52
 53
 54
 55
 56
 57
 58
 59
 60
 61
 62
 63
 64
 65
 66
 67
 68
 69
 70
 71
 72
 73
 74
 75
 76
 77
 78
 79
 80
 81
 82
 83
 84
 85
 86
 87
 88
 89
 90
 91
 92
 93
 94
 95
 96
 97
 98
 99
 100
 101
 102
 103
 104
 105
 106
 107
 108
 109
 110
 111
 112
 113
 114
 115
 116
 117
 118
 119
 120
 121
 122
 123
 124
 125
 126
 127
 128
 129
 130
 131
 132
 133
 134
 135
 136
 137
 138
 139
 140
 141
 142
 143
 144
 145
 146
 147
 148
 149
 150
 151
 152
 153
 154
 155
 156
 157
 158
 159
 160
 161
 162
 163
 164
 165
 166
 167
 168
 169
 170
 171
 172
 173
 174
 175
 176
 177
 178
 179
 180
 181
 182
 183
 184
 185
 186
 187
 188
 189
 190
 191
 192
 193
 194
 195
 196
 197
 198
 199
 200
 201
 202
 203
 204
 205
 206
 207
 208
 209
 210
 211
 212
 213
 214
 215
 216
 217
 218
 219
 220
 221
 222
 223
 224
 225
 226
 227
 228
 229
 230
 231
 232
 233
 234
 235
 236
 237
 238
 239
 240
 241
 242
 243
 244
 245
 246
 247
 248
 249
 250
 251
 252
 253
 254
 255
 256
 257
 258
 259
 260
 261
 262
 263
 264
 265
 266
 267
 268
 269
 270
 271
 272
 273
 274
 275
 276
 277
 278
 279
 280
 281
 282
 283
 284
 285
 286
 287
 288
 289
 290
 291
 292
 293
 294
 295
 296
 297
 298
 299
 300
 301
 302
 303
 304
 305
 306
 307
 308
 309
 310
 311
 312
 313
 314
 315
 316
 317
 318
 319
 320
 321
 322
 323
 324
 325
 326
 327
 328
 329
 330
 331
 332
 333
 334
 335
 336
 337
 338
 339
 340
 341
 342
 343
 344
 345
 346
 347
 348
 349
 350
 351
 352
 353
 354
 355
 356
 357
 358
 359
 360
 361
 362
 363
 364
 365
 366
 367
 368
 369
 370
 371
 372
 373
 374
 375
 376
 377
 378
 379
 380
 381
 382
 383
 384
 385
 386
 387
 388
 389
 390
 391
 392
 393
 394
 395
 396
 397
 398
 399
 400
 401
 402
 403
 404
 405
 406
 407
 408
 409
 410
 411
 412
 413
 414
 415
 416
 417
 418
 419
 420
 421
 422
 423
 424
 425
 426
 427
 428
 429
 430
 431
 432
 433
 434
 435
 436
 437
 438
 439
 440
 441
 442
 443
 444
 445
 446
 447
 448
 449
 450
 451
 452
 453
 454
 455
 456
 457
 458
 459
 460
 461
 462
 463
 464
 465
 466
 467
 468
 469
 470
 471
 472
 473
 474
 475
 476
 477
 478
 479
 480
 481
 482
 483
 484
 485
 486
 487
 488
 489
 490
 491
 492
 493
 494
 495
 496
 497
 498
 499
 500
 501
 502
 503
 504
 505
 506
 507
 508
 509
 510
 511
 512
 513
 514
 515
 516
 517
 518
 519
 520
 521
 522
 523
 524
 525

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

6.0 SAFETY DURING MAINTENANCE

No special safety conditions are required for maintenance of the landfill cover other than caution while operating machinery and not working within the sedimentation pond while it is full of water.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

7.0 REQUIRED EQUIPMENT

It is anticipated that Waste Management of Wisconsin will have a contractor perform maintenance activities for the site rather than keep equipment at the site. Maintenance activity frequency will be low enough that dedicated mowing and earth-moving equipment for the site would not be economically prudent.

A vertical strip of ten small, rectangular, black-and-white images, likely film frames or microfilm segments. The images show various patterns and textures, including horizontal lines, vertical lines, and abstract shapes. The strip is oriented vertically and appears to be a scan of a physical medium.

**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

8.0 OPERATION AND MAINTENANCE ANNUAL BUDGET

The following table lists anticipated maintenance, testing, and monitoring activities and the quantities, unit prices, and extensions for each, if required.

Table C-3
MAINTENANCE ANNUAL BUDGET
Operation and Maintenance Plan, Landfill Cover RD/RA

| ITEM | QUANTITY | UNIT PRICE | ANNUAL COST |
|---|----------|-------------|-------------|
| Cap Monitoring | 72 hours | \$ 50.00 | \$ 3,600 |
| Cap Maintenance | | | |
| Repair & Regrade Eroded Portions of Cap (1 ac/yr, 1 ft depth) | 1610 cy | \$ 1.50 | \$ 2,415 |
| Reseed & Mulch | 2420 sy | \$ 0.35 | \$ 850 |
| Mowing | 6 ac | \$ 45.00 | \$ 270 |
| Fertilize | 6 ac | \$ 140.00 | \$ 840 |
| Clean Swales and Sediment Basin | 1 L.S. | \$ 500.00 | \$ 500 |
| Annual O&M Report | 1 L.S. | \$ 6,000.00 | \$ 6,000 |
| SUBTOTAL | | | \$ 14,475 |
| CONTINGENCY (15%) | | | \$ 2,175 |
| TOTAL | | | \$ 16,650 |



**OPERATION AND MAINTENANCE PLAN
RD/RA DESIGN REPORT
LANDFILL COVER DESIGN
HAGEN FARM SITE**

9.0 RECORDKEEPING

Recordkeeping for the landfill cover system will consist of preparation of an annual report to be submitted to WDNR and U.S. EPA. The following items will be included in the report.

- Monitoring activities including a description of the soil cap and erosion and sediment control structures at the time of each semi-annual inspection. If additional inspections were performed due to significant storm events, the condition of the landfill cover and erosion and sediment control structures will be described for each storm-related inspection.
- Date and results of routine maintenance activities such as mowing and fertilizing.
- Date and description of activities for repairs and reseeding. The description will include the materials used and the location.
- A description of the test results for the annual topsoil testing.

